

**Multi Room Modular Construction System (MRMC)**

The MRMC System utilizes precast concrete modules to bring to high-rise construction the benefits of modular construction, mainly shorter construction time and lower cost. The precast concrete modules are cast on production lines at a rate of one unit every four hours. The modules are outfitted at ground level with all interior systems such as partitions and utilities. The modules are then stacked on each other and behave structurally like a multitude of tubes without well defined structural frames.

Contact:                    Dong-In Shin  
Organization:            D.I. Shin International Inc.  
Address:                    1164 Bishop Suite #1012  
City:                        Honolulu  
State/Province:         HI  
Postal Code:             96813  
Country:                    USA  
Phone No:                 808-536-2702  
FAX:                        808-531-7059  
URL:  
Email: